# Bundoran Waste Water treatment Works Long Sea Outfall

#### **Project Summary**

Irish Water are currently constructing a new Waste water Treatment Works (WwTW) to serve the town of Bundoran in County Donegal, Ireland. BAM Civils have been commissioned as principle contractor for construction of the WwTW together with all associated pipework.

BAM Civils appointed AMS No Dig Ltd to design and build the outfall section of 560mm pipeline which was to pass under the sea wall at Pollbrean terminating on the sea bed 10m below the mean low water level 584m off shore in Donegal Bay.

The main considerations when designing the outfall were:

- 1. Ensuring the environmental impact of the work was kept to an absolute minimum.
- 2. Ensuring the design provided a sound hydraulic solution

HDD was selected as the construction technique as it was the most cost effective solution and produced less environmental impact than alternative installation techniques.

The design, planning and approval process took two years to complete before construction commenced in January 2017. AMS prepared detailed construction proposals including all calculations necessary to gain construction approval from the stake holders.

### **Pilot Stage**

The Drill Guide Gyro guidance system, mud motor bottom hole assembly (BHA) fitted with a tri-cone drill bit was used to construct the pilot which was terminated 10m short of the punch out point on the sea floor within the bay.

## **Delayed Punch Out**

The punch-out of the bore hole refers to reaching the target location for the HDD exit point. Once a borehole reaches its destination on the seabed, the drill path on an outfall project effectively becomes an uninterrupted tunnel to the ocean. After this stage, any drilling operations inside the hole will result in some form of discharge from the borehole into the marine environment of cuttings and drilling fluid.

To mitigate the effect of the HDD works on the environment AMS chose to delay this part of the operation where the borehole was drilled out to the seabed. The aim was to maximise the operational time where the borehole was a closed system whereby drilling fluid, cuttings and spoil remained in a recyclable loop back to the rig positioned on shore.

The major benefits of delaying the punch-out were:

- Increased speed of operation
- Consumption of drilling fluid products was greatly minimised
- Discharge of Bentonite based drilling fluid and cuttings into marine environment was considerably reduced
- Reduced water consumption

#### **Upsizing the Borehole**

Verification of the survey data and validation of the pilot hole delayed punch-out location was confirmed before commencement of reaming operations.

The reaming assembly was used in a forward mode of operation and not the conventional pull-reaming mode. Forward reaming is more commonly used for outfall projects and greatly reduces the need for offshore vessel support associated with the back reaming (pull-reaming) method. The borehole data provided pre-construction indicated forward reaming could be safely undertaken in the consolidated formation expected.

Once the reaming and hole cleaning stage was completed the punch out assembly was re-introduced to the blind end of the hole for final punch out.

### **Pipe Installation**

AMS prepared the pipe for installation which included welding, de beading, and Hydrostatic testing of two 300m sections of pipe.

After the drill pipe and BHA was withdrawn from the borehole the drill rig was removed and the pipe pusher was positioned and anchored. The pre-fabricated length of pipe was maneuvered and fed through the pipe pusher using mechanical lifting methods and pipe conveyors.

The pipe was pushed into position over a three hour period which included welding the two sections of pipe together midway through the operation. The pipe push was complete when the pushing head emerged from the borehole on the sea bed which was confirmed by divers.



Site Setup

Prime PD250 Drill Rig in position



Pipe installation overview with Pipe Pusher in position

**Pipe Installation Overview** 



**Pipe Installation Complete**